

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,


Tender No: BBMP/EE/DD/TEN/05/12-13 Date: 29.09.2012


Item No: 30

SCHDULE-B

NAME OF WORK: Improvements to Roads & Drains at BTS Layout in W No.14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Scarifying kankar / gravel / metal crust upto 150mm thick with pick axes and disposal of stuff within a lead of 100 meters including cost of all labour charges Complete as per specifications.	Sqm	2811.50	22.00	Rupees Twenty Two Only
2	Construction of embankment with approved material Gravel/Murram with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications.	Cum	801.10	151.00	Rupees One Hundred Fifty One Only
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Complete as per Specification.	Cum	281.15	1120.00	Rupees One Thousand One Hundred Twenty Only
4	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Complete as per Specification.	Cum	210.86	1200.00	Rupees One Thousand Two Hundred Only
5	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	294.30	96.00	Rupees Ninety Six Only
6	Removing B.S.Slab of drain and stacking etc. Complete as per specifications.	Sqm	1798.50	53.00	Rupees Fifty Three Only


Signature of the Contractor


Executive Engineer

7	Refixing stone slabs of drains and pointing in CM 1:3 etc. Complete as per specifications.	Sqm	1798.50	62.00	Rupees Sixty Two Only
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 15 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	716.03	80.00	Rupees Eighty Only


 Signature of the Contractor


 Executive Engineer,
 Dasarahalli Division,